

the instructions of the client for their sole and specific use

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at

SPECIFICATION FOR DL-TLG200 TELESCOPIC LIFTING UNIT

• MAXIMUM SAFE WORKING LOAD (SWL) AT TOP OF TELESCOPIC

CYLINDER
STAGE 1 = 50 TONNES @ 75 BAR WORKING PRESSURE
STAGE 2 = 50 TONNES @ 130 BAR WORKING PRESSURE
SEE DRAWING DL-TLG200-005 FOR DETAILS OF LIFTING
ARRANGEMENTS AND DUTY CHARTS

- TESTS CARRIED OUT AT FULL EXTENSION FOR BOTH TELESCOPIC CYLINDER STAGES)
- PYNAMIC TEST LOAD = 1.10 x SWL (TESTS CARRIED OUT FOR BOTH TELESCOPIC CYLINDER STAGES AND FOR ALL FUNCTIONS)
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION (SEE OPERATION AND MAINTENANCE MANUAL FOR DETAILS).
- AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)

- LIFTING AND LOWERING SPEED OF TELESCOPIC CYLINDER = 0.5 m/minute (FAST) AND 0.1 m/minute (SLOW) CONSTANT FOR BOTH

- CONTROL FOR ALL FUNCTIONS = CENTRAL WIRELESS CONTROL CONSOLE OR CONTROL PANEL AT THE CENTRAL CONTROL UNIT OR LOCAL CONTROL PANEL AT EACH DL-TLG200 LIFTING UNIT
- COMPLETE DL-TLG200 LIFTING UNIT LAID ON END AS SHOWN FOR RANSPORT IN A STANDARD SHIPPING CONTAINER

= 1,030 kg= 330 kg = 230 kg = 300 kg = 1,400 kg = 105 kg

= 3,685 kg




DLT Engineering International House Midland Road, Higham Ferrers Northamptonshire, NN10 8DN United Kingdom Tel: +44 (0) 1933 319133


www.dlteng.com


N1

DL-TLG200 TELESCOPIC LIFTING UNIT GENERAL ARRANGEMENT AND SPECIFICATION


- 1	d	<i>p</i>	$\overline{}$	Design Eng:	PD	Checking Eng:	JM
- 1	V	$\overline{\mathcal{F}}$		Drawn by:	AW	Project Eng:	SAB
ı	Scales			Drawing Status			
	(At A3)	AS	SHOWN	INF	ORN	MATION	







2.8m STANDARD TRACK SECTION



THE MAXIMUM WHEEL LOADS AND BEARING PAD LOADS AND PRESSURES TABULATED BELOW ASSUME 5% HORIZONTAL LOAD PLUS 1% SLOPE OF THE TRACK, BOTH AT 45% ORIENTATION. THE PROJECT SPECIFIC VALUES WILL DEPEND ON THE ACTUAL LOADS TO BE APPLIED TO THE SYSYEM. SEE OPERATION AND MAINTENANCE MANUAL FOR FURTHER INFORMATION.

DL-TLG200 Standard Track - Maximum Loads					
	Telescopic Cylinder Stage 1	Telescopic Cylinder Stage 2			
Maximum Wheel Load on Track	22.3 Tonnes	27.6 Tonnes			
Maximum Load on each Bearing Pad	22.9 Tonnes	28.2 Tonnes			
Maximum Average Bearing Pressure under each Bearing Pad	3.3 MPa	4.0 MPa			
Maximum Peak Bearing Pressure under each Bearing Pad	7.4 MPa	8.7 MPa			

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

SPECIFICATION FOR DL-TLG200 STANDARD TRACK SECTIONS

- STANDARD TRACK SECTIONS SUPPLIED IN LENGTHS GIVING EFFECTIVE TRACK LENGTHS OF 5.6m AND 2.8m (OVERALL LENGTHS OF 5,803mm AND 3,003mm)
- STANDARD TRACK SECTIONS SUPPLIED WITH RAILS AT 1.4m CENTRES
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- SEE TABLE FOR MAXIMUM WHEEL LOADS AND BEARING PAD LOADS AND PRESSURES
- OPERATING TEMPERATURE = -20 to +45 °C
- STANDARD TRACK SECTIONS ARE SUITABLE FOR TRANSPORT IN STANDARD SHIPPING CONTAINERS
- WEIGHTS

5.6m LONG STANDARD TRACK SECTION = 1,210 kg

2.8m LONG STANDARD TRACK SECTION = 665 kg



DLT Engineering International House Midland Road, Higham Ferrers Northamptonshire, NN10 8DN United Kingdom Tel: +44 (0) 1933 319133

ununu ditana aa

Project
DL-TLG200
TELESCOPIC LIFTING GANTRY

DL-TLG200 STANDARD TRACK SECTIONS
GENERAL ARRANGEMENT AND SPECIFICATION

Design Eng: PD Checking Eng: JM Drawn by: AW Project Eng: SAB

Cales (At A3) AS SHOWN


Design Eng: PD Checking Eng: JM Project Eng: SAB

Drawing Status

INFORMATION

Original Drawing size: A3

DL-TLG200-004



2 No LIFT POINTS LOADED PER HEAD BEAM STAGES 0 TO 2 : HEAD BEAM IN OPERATIONAL RANGE FROM LEVEL 3115 TO LEVEL 7115

SAFE WORKING LOAD (SWL) AT SPECIFIED SPAN								
PER LIFT POINT [TONNES]								
LIFT POINTS SPACING	POINTS LOAD CENTRE OFFSET E [m] FROM							
LPS [m]	0.00	1.00	2.00	3.00	4.00			
		SPAN 11	.40m					
1.20	44.0	39.1	33.8	29.7	26.5			
2.00 to 9.00	46.2	39.1	33.8	29.7	26.5			
	SPAN 10.00m							
1.20 to 9.00	46.2	38.2	32.5	28.3	-			
	SPAN 9.00m							
1.20 to 8.00	46.2	37.5	31.5	27.1	-			
		SPAN 8.	00m					
1.20 to 7.00	46.2	36.6	30.3	-	-			
	SPAN 7.00m							
1.20 to 6.00	46.2	35.6	28.8	-	-			
SPAN 6.00m								
1.20 to 5.00	46.2	34.3	-	-	-			
SPAN 5.00m								
1.20 to 4.00	46.2	-	-	-	-			

SINGLE LIFT POINT LOADED PER HEAD BEAM
STAGES 0 TO 2 : HEAD BEAM IN OPERATIONAL RANGE
FROM LEVEL 3115 TO LEVEL 7115

SAFE	SAFE WORKING LOAD (SWL) AT SPECIFIED SPAN							
	PER LIFT POINT [TONNES]							
	SINGLE LIFT POINT LOADED							
SPAN	SPAN LIFT POINT OFFSET E[m] FROM SPAN CENTRE							
[m]	0.00	1.00	2.00	3.00	4.00			
11.40	50.0	50.0	50.0	50.0	50.0			
10.00	50.0	50.0	50.0	50.0	50.0			
9.00	50.0	50.0	50.0	50.0	48.9			
8.00	50.0	50.0	50.0	50.0	-			
7.00	50.0	50.0	50.0	49.7	-			
6.00	50.0	50.0	50.0	-	-			
5.00	50.0	50.0	-	-	-			

INTERPOLATION BETWEEN TABULATED VALUES PERMISSABLE SEE ALSO OPERATION AND MAINTENANCE MANUAL

O NOT SCALE This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

DUTY CHARTS ASSUME THE FOLLOWING:-

- STANDARD DL-TLG200 COMPONENTS WITH DL-TLG200 HEAD BEAM
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%
- DL-TLG200 STANDARD TRACK SECTIONS USED
- TABULATED LOADS APPLIED TO SHACKLE OR, IF SHACKLE NOT USED, TO SHACKLE BEAM

IF THE DL-TL200 TELESCOPIC LIFTING
GANTRY IS TO BE USED IN A
CONFIGURATION NOT SHOWN ON THIS
DRAWING, CONTACT DLT ENGINEERING
FOR SPECIFIC SAFE WORKING LOADS AND
ANY SPECIAL CONDITIONS THAT MAY APPLY



DLT Engineering International House Midland Road, Higham Ferrers Northamptonshire, NN10 8DN United Kingdom Tel: +44 (0) 1933 319133

www.dlteng.com

N1

DL-TLG200 TELESCOPIC LIFTING GANTRY

LIFTING ARRANGEMENT AND DUTY CHARTS 2 No. LIFT POINTS LOADED PER HEAD BEAM SINGLE LIFT POINT LOADED PER HEAD BEAM

1 6	₩.	$\overline{}$	Design Eng:	JM	Checking Eng:	PD
7	Ø	\Box	Drawn by:	AW	Project Eng:	SAB
Scales (At A3)	AS	SHOWN	Drawing Status	ORN	MATIO	7
Origina	Draw	ing size: A3				
Drawing	NΙο					Pov

DL-TLG200-005