

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

SPECIFICATION FOR DL-TLG400, 4-POINT LIFT SYSTEM

• MAXIMUM SAFE WORKING LOAD (SWL) AT TOP OF TELESCOPIC CYLINDERS
STAGE 1 = 400 TONNES @ 83 BAR WORKING PRESSURE
STAGE 2 = 400 TONNES @ 120 BAR WORKING PRESSURE
STAGE 3 = 280 TONNES @ 120 BAR WORKING PRESSURE
SEE DRAWINGS DL-TLG400-005-01 AND 02 FOR LIFTING ARRANGEMENTS AND DUTY CHARTS

• STATIC TEST LOAD = 1.25 x SWL + MAXIMUM HORIZONTAL LOAD (TESTS CARRIED OUT AT FULL EXTENSION FOR EACH TELESCOPIC CYLINDER STAGE)
• DYNAMIC TEST LOAD = 1.10 x SWL (TESTS CARRIED OUT FOR EACH TELESCOPIC CYLINDER STAGE AND FOR ALL FUNCTIONS)

• MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION (SEE OPERATION AND MAINTENANCE MANUAL FOR DETAILS)

• MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)

• MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%

• MAXIMUM WHEEL LOAD = 53 TONNES

• LIFTING AND LOWERING SPEED OF TELESCOPIC CYLINDER = 0.5 m/minute (FAST) AND 0.1 m/minute (SLOW) - CONSTANT FOR ALL TELESCOPIC CYLINDER STAGES

• LONGITUDINAL MOVEMENT SPEED OF DL-TLG400 LIFTING UNITS = 3.0 m/minute (FAST) AND 1.0 m/minute (SLOW)

• TRANSVERSE MOVEMENT SPEED OF DL-TLG400 POWERED TROLLEYS = 0.5 m/minute

• POWER SUPPLY = 380-420 VOLTS AT 50 Hz OR 440-480 VOLTS AT 60 Hz, 3 PHASE + EARTH
• MAXIMUM POWER CONSUMPTION = 10 kW RUNNING PER DL-TLG400 LIFTING UNIT

• CONTROL FOR ALL FUNCTIONS = CENTRAL WIRELESS CONTROL CONSOLE OR CONTROL PANEL AT THE CENTRAL CONTROL UNIT OR LOCAL CONTROL PANEL AT EACH DL-TLG400 LIFTING UNIT

• OPERATING TEMPERATURE = -20 TO +45 °C SUBJECT TO HYDRAULIC OIL GRADE USED

• ALL COMPONENTS OF DL-TLG400 SYSTEM SUITABLE FOR TRANSPORT IN STANDARD SHIPPING CONTAINERS

MAIN FEATURES

- 400 TONNES LIFTING CAPACITY ON FOUR LIFTING UNITS
- 100 TONNES LIFTING CAPACITY PER LIFTING UNIT
- HIGH HORIZONTAL LOAD CAPACITY
- ADJUSTABLE TRACK WIDTH FOR INCREASED STABILITY
- TRACKS CAN BE AT DIFFERENT LEVELS
- CENTRAL WIRELESS CONTROL OF ALL FUNCTIONS
- ACCURATE ADJUSTMENT OF THE LOAD POSITION TO +/-1mm IN ALL DIRECTIONS
- ALL COMPONENTS SUBJECT TO STATIC TEST AT 125% OF SWL AND DYNAMIC TESTS OF ALL FUNCTIONS AT 110% OF SWL IN ACCORDANCE WITH APPROPRIATE EUROPEAN DIRECTIVES
- ALL COMPONENTS AND COMPLETE DL-TLG400 SYSTEM CE MARKED IN ACCORDANCE WITH APPROPRIATE EUROPEAN DIRECTIVES
- ALL COMPONENTS SUITABLE FOR TRANSPORT IN STANDARD SHIPPING CONTAINERS

2 No. DL-TLG400 POWERED TROLLEYS PER HEAD BEAM WITH CHAIN DRIVE FOR SECURE LATERAL MOVEMENT. SAFE WORKING LOAD 100 TONNES PER UNIT SEE DRG DL-TLG400-003-01

DL-TLG400 HEAD BEAM TO SUIT TRACK CENTRES UP TO 11.3m SEE DRGS DL-TLG400-003-01 & 02

POWER AND CONTROL CABLES TO DL-TLG400 LIFTING UNITS (BY DLT)


CENTRAL CONTROL UNIT (BY DLT) COMPRISING POWER DISTRIBUTION CABINET AND PLC CABINET

POWER IN (BY OTHERS) 40 kW MAX RUNNING

DL-TLG400 STANDARD TRACK SECTIONS AVAILABLE IN 2.8m AND 5.6m LENGTHS SEE DRG DL-TLG40-004

WIRELESS CONTROL CONSOLE LINKED TO CENTRAL CONTROL UNIT

4 No. DL-TLG400 LIFTING UNITS EACH WITH 3 STAGE TELESCOPIC CYLINDER. SAFE WORKING LOAD 100, 100 AND 70 TONNES PER UNIT FOR TELESCOPIC CYLINDER STAGES 1, 2 AND 3 SEE DRG DL-TLG400-002



TRANSVERSE
LONGITUDINAL

NOTE:
HEAD BEAMS WITH POWERED TROLLEYS SHOWN.
HEAD BEAMS WITH STATIC HANGERS AVAILABLE.
SEE DRG DL-TLG400-003-02

DLT Engineering
International House
Midland Road, Higham Ferrers
Northamptonshire, NN10 8DN
United Kingdom
Tel: +44 (0) 1933 319133
www.dlteng.com

Project
DL-TLG400
TELESCOPIC LIFTING GANTRY

Drawing Title
4 POINT TELESCOPIC LIFTING GANTRY
GENERAL ARRANGEMENT AND SPECIFICATION

Design Eng: JM	Checking Eng: PD
Drawn by: SG	Project Eng: SAB

Original Drawing size: A3	Drawing Status INFORMATION
---------------------------	--------------------------------------

Drawing No. DL-TLG400-001	Rev. N1
-------------------------------------	-------------------

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.




Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

SPECIFICATION FOR DL-TLG400 TELESCOPIC LIFTING UNIT

- MAXIMUM SAFE WORKING LOAD (SWL) AT TOP OF TELESCOPIC CYLINDER
STAGE 1 = 100 TONNES @ 83 BAR WORKING PRESSURE
STAGE 2 = 100 TONNES @ 120 BAR WORKING PRESSURE
STAGE 3 = 70 TONNES @ 120 BAR WORKING PRESSURE
SEE DRAWINGS DL-TLG400-005-01 AND 02 FOR DETAILS OF LIFTING ARRANGEMENTS AND DUTY CHARTS
- TELESCOPIC CYLINDER WORKING PRESSURE ON RETRACT = 70 BAR
- STATIC TEST LOAD = 1.25 x SWL + MAXIMUM LATERAL LOAD (TESTS CARRIED OUT AT FULL EXTENSION FOR EACH TELESCOPIC CYLINDER STAGE)
- DYNAMIC TEST LOAD = 1.10 x SWL (TESTS CARRIED OUT FOR EACH TELESCOPIC CYLINDER STAGE AND FOR ALL FUNCTIONS)
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION (SEE OPERATION AND MAINTENANCE MANUAL FOR DETAILS).
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- THE MAXIMUM % TIPPING FIGURES GIVEN FOR STAGES 1, 2 AND 3 ASSUME 5% LATERAL LOAD AT THE ROCKER JOINT PLUS 1% TRANSVERSE SLOPE OF THE TRACK
- MAXIMUM WHEEL LOAD = 53 TONNES
- LIFTING AND LOWERING SPEED OF TELESCOPIC CYLINDER = 0.5 m/minute (FAST) AND 0.1 m/minute (SLOW) - CONSTANT FOR ALL TELESCOPIC CYLINDER STAGES
- LONGITUDINAL MOVEMENT SPEED OF DL-TLG400 LIFTING UNITS = 3.0 m/minute (FAST) AND 1.0 m/minute (SLOW)
- POWER SUPPLY = 380-420 VOLTS AT 50 Hz OR 440-480 VOLTS AT 60 Hz, 3 PHASE + EARTH
- MAXIMUM POWER CONSUMPTION = 10 kW RUNNING PER DL-TLG400 LIFTING UNIT
- CONTROL FOR ALL FUNCTIONS = CENTRAL WIRELESS CONTROL CONSOLE OR CONTROL PANEL AT THE CENTRAL CONTROL UNIT OR LOCAL CONTROL PANEL AT EACH DL-TLG400 LIFTING UNIT
- OPERATING TEMPERATURE = -20 TO +45 °C
SUBJECT TO HYDRAULIC OIL GRADE USED
- TELESCOPIC CYLINDER FOLDS AS SHOWN SO THAT COMPLETE DL-TLG400 LIFTING UNIT (WITH BOGIE EXTENSION PIECES) IS SUITABLE FOR TRANSPORT IN A STANDARD SHIPPING CONTAINER
- WEIGHTS
BASE UNIT - STEEL FRAME AND PINS = 2,645 kg
BASE UNIT - DRIVEN BOGIES (2 x 425 kg) = 850 kg
BASE UNIT - UN-DRIVEN BOGIES (2 x 265 kg) = 530 kg
BASE UNIT - OTHER EQUIPMENT = 800 kg
TELESCOPIC CYLINDER = 2,670 kg
ROCKER JOINT ASSEMBLY = 205 kg
HYDRAULIC OIL = 650 kg
TOTAL = 8,350 kg
- HYDRAULIC OIL TANK SIZE = 2 x 350 litres = 700 litres



ROCKER JOINT
3 STAGE TELESCOPIC CYLINDER DESIGNED FOR 5% HORIZONTAL LOAD AT FULL EXTENSION AND FOR THE STAGES TO EXTEND AND RETRACT IN THE CORRECT SEQUENCE UNDER LOAD





TURNING RAM TO CHANGE BETWEEN TRANSPORT AND OPERATING CONFIGURATIONS

ELECTRIC CABINET WITH LOCAL CONTROL PANEL


ELECTRIC MOTOR AND HYDRAULIC PUMP

2 No HYDRAULIC OIL TANKS



DIMENSIONS FOR TRANSPORT



DIMENSIONS FOR OPERATION



UNDERSIDE OF HEAD BEAM



UNIT FOLDED FOR TRANSPORT

STAGE 3
CAPACITY: 70 Tonnes (EACH UNIT)
MAX % TIPPING = 61%

STAGE 2
CAPACITY: 100 Tonnes (EACH UNIT)
MAX % TIPPING = 50%

STAGE 1
CAPACITY: 100 Tonnes (EACH UNIT)
MAX % TIPPING = 61%

STAGE 0

DLT Engineering
International House
Midland Road, Higham Ferrers
Northamptonshire, NN10 8DN
United Kingdom
Tel: +44 (0) 1933 319133
www.dlteng.com

Project
DL-TLG400
TELESCOPIC LIFTING GANTRY

Drawing Title
DL-TLG400 TELESCOPIC LIFTING UNIT
GENERAL ARRANGEMENT AND SPECIFICATION

Design Eng: PD	Checking Eng: JM
Drawn by: AW	Project Eng: SAB

Scales (At A3): AS SHOWN	Drawing Status: INFORMATION
--------------------------	-----------------------------

Original Drawing size: A3	Drawing No. DL-TLG400-002	Rev. N1
---------------------------	---------------------------	---------

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.
 DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.
 Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

SPECIFICATION
 DL-TLG400 HEAD BEAM AND
 DL-TLG400 POWERED TROLLEYS

- MAXIMUM SAFE WORKING LOAD (SWL) = 100 TONNES PER LIFT POINT = 190 TONNES PER HEAD BEAM
 SEE DRAWINGS DL-TLG400-005-01 AND 02 FOR LIFTING ARRANGEMENTS AND DUTY CHARTS
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION
- MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%
- TRANSVERSE MOVEMENT SPEED OF DL-TLG400 POWERED TROLLEYS = 0.5 m/minute

- POWER SUPPLY = 380-420 VOLTS AT 50 Hz OR 440-480 VOLTS AT 60 Hz, 3 PHASE+EARTH
- MAXIMUM POWER CONSUMPTION = 0.5 kW RUNNING PER DL-TLG400 POWERED TROLLEY

- CONTROL FOR ALL FUNCTIONS = CENTRAL WIRELESS CONTROL CONSOLE OR CONTROL PANEL AT THE CENTRAL CONTROL UNIT OR LOCAL CONTROL PANEL AT EACH DL-TLG400 LIFTING UNIT

- OPERATING TEMPERATURE = -20 to +45°C

- DL-TLG400 HEAD BEAM SUPPORTED ON 2 No. SUPPORT STOOL ASSEMBLIES AND COMPLETE WITH ALL EQUIPMENT IS SUITABLE FOR TRANSPORT IN A STANDARD 40' SHIPPING CONTAINER


- WEIGHTS
 DL-TLG400 HEAD BEAM = 6,270 kg
 POWERED TROLLEY = 2x1,635 kg
 CHAIN AND CHAIN ANCHORAGES = 440 kg
 TRANSPORT SUPPORT STOOLS = 2 x 210 kg

- TOTAL OPERATING WEIGHT = 9,980 kg
 TOTAL TRANSPORT WEIGHT = 10,400 kg

DLT Engineering
 International House
 Midland Road, Higham Ferrers
 Northamptonshire, NN10 8DN
 United Kingdom
 Tel: +44 (0) 1933 319133
 www.dlteng.com


Project
 DL-TLG400
 TELESCOPIC LIFTING GANTRY

Drawing Title
 DL-TLG400 HEAD BEAM AND
 DL-TLG400 POWERED TROLLEYS
 GENERAL ARRANGEMENT AND SPECIFICATION


	Design Eng: JM	Checking Eng: PD
	Drawn by: SG	Project Eng: SAB

Scales (At A3) AS SHOWN
 Drawing Status
INFORMATION


Original Drawing size: A3
 Drawing No. DL-TLG400-003-01
 Rev. N1




HEAD BEAM ASSEMBLY IN LIFTING CONFIGURATION
 OPERATIONAL WEIGHT 9.98 TONNES



POWERED TROLLEY
 (HEAD BEAM OMITTED FOR CLARITY)



HEAD BEAM ASSEMBLY IN LIFTING CONFIGURATION



HEAD BEAM ASSEMBLY IN TRANSPORT CONFIGURATION
 TRANSPORT WEIGHT 10.40 TONNES

A-A (1 : 50)

END ELEVATION (1 : 50)

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.
 DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.
 Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES


SPECIFICATION
 DL-TLG400 HEAD BEAM AND
 DL-TLG400 STATIC HANGERS

- MAXIMUM SAFE WORKING LOAD (SWL) = 100 TONNES PER LIFT POINT = 192 TONNES PER HEAD BEAM
 SEE DRAWINGS DL-TLG400-005-01 AND 02 FOR LIFTING ARRANGEMENTS AND DUTY CHARTS
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION
- MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%
- OPERATING TEMPERATURE = -20 to +45°C

• DL-TLG400 HEAD BEAM SUPPORTED ON 2 No. SUPPORT STOOL ASSEMBLIES AND COMPLETE WITH ALL EQUIPMENT IS SUITABLE FOR TRANSPORT IN A STANDARD 40' SHIPPING CONTAINER


- WEIGHTS
 DL-TLG400 HEAD BEAM = 6,270 kg
 STATIC HANGER ASSEMBLY = 2x 650 kg
 TRANSPORT SUPPORT STOOLS = 2 x 210 kg

TOTAL OPERATING WEIGHT = 7,570 kg
 TOTAL TRANSPORT WEIGHT = 7,990 kg




A-A (1 : 50)


HEAD BEAM ASSEMBLY IN LIFTING CONFIGURATION
 OPERATIONAL WEIGHT 7.570 TONNES



STATIC HANGER
 (HEAD BEAM OMITTED FOR CLARITY)



HEAD BEAM ASSEMBLY IN LIFTING CONFIGURATION



END ELEVATION (1 : 50)

HEAD BEAM ASSEMBLY IN TRANSPORT CONFIGURATION
 TRANSPORT WEIGHT 7.990 TONNES

DLT Engineering
 International House
 Midland Road, Higham Ferrers
 Northamptonshire, NN10 8DN
 United Kingdom
 Tel: +44 (0) 1933 319133
 www.dlteng.com

Project
 DL-TLG400
 TELESCOPIC LIFTING GANTRY

Drawing Title
 DL-TLG400 HEAD BEAM AND
 DL-TLG400 STATIC HANGERS
 GENERAL ARRANGEMENT AND SPECIFICATION

	Design Eng: JM	Checking Eng: PD
	Drawn by: SG	Project Eng: SAB
Scales (At A3) AS SHOWN	INFORMATION	
Original Drawing size: A3		

Drawing No. **DL-TLG400-003-02** Rev. **N1**

DO NOT SCALE






This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.
 DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.
 Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.

Copyright © DLT Engineering Ltd.

NOTES

SPECIFICATION FOR DL-TLG400 STANDARD TRACK SECTIONS

- STANDARD TRACK SECTIONS SUPPLIED IN LENGTHS GIVING EFFECTIVE TRACK LENGTHS OF 5.6m AND 2.8m (OVERALL LENGTHS OF 5,803mm AND 3,003mm)
- STANDARD TRACK SECTIONS SUPPLIED WITH RAILS AT 1.0m CENTRES AND WITH INSERT PIECES TO INCREASE RAILS TO 1.7m CENTRES
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- SEE TABLE FOR MAXIMUM WHEEL LOADS AND BEARING PAD LOADS AND PRESSURES
- OPERATING TEMPERATURE = -20 TO +45°C
- FULLY ASSEMBLED STANDARD TRACK SECTIONS ARE SUITABLE FOR TRANSPORT IN STANDARD SHIPPING CONTAINERS
- WEIGHTS
 5.6m LONG x 1.0m RAIL CENTRES = 1,400 kg
 5.6m LONG x 1.7m RAIL CENTRES = 1,470 kg
 2.8m LONG x 1.0m RAIL CENTRES = 760 kg
 2.8m LONG x 1.7m RAIL CENTRES = 810 kg



THE MAXIMUM WHEEL LOADS AND BEARING PAD LOADS AND PRESSURES TABULATED BELOW ASSUME 5% HORIZONTAL LOAD PLUS 1% SLOPE OF THE TRACK, BOTH AT 45 DEGREES ORIENTATION. THE PROJECT SPECIFIC VALUES WILL DEPEND ON THE ACTUAL LOADS TO BE APPLIED TO THE SYSTEM. SEE OPERATION AND MAINTENANCE MANUAL FOR FURTHER INFORMATION.

DL-TLG400 Standard Track - Maximum Loads			
	Telescopic Cylinder Stage 1 1.0m Rail Centres	Telescopic Cylinder Stage 2 1.7m Rail Centres	Telescopic Cylinder Stage 3 1.7m Rail Centres
Maximum Wheel Load on Track	53.1 Tonnes	52.7 Tonnes	40.1 Tonnes
Maximum Load on each Bearing Pad	53.5 Tonnes	53.1 Tonnes	40.3 Tonnes
Maximum Average Bearing Pressure under each Bearing Pad	6.7 MPa	6.7 MPa	5.1 MPa
Maximum Peak Bearing Pressure under each Bearing Pad	9.1 MPa	9.0 MPa	6.4 MPa

DLT Engineering
International House
Midland Road, Higham Ferrers
Northamptonshire, NN10 8DN
United Kingdom
Tel: +44 (0) 1933 319133
www.dlteng.com

Project
DL-TLG400
TELESCOPIC LIFTING GANTRY

Drawing Title
DL-TLG400 STANDARD TRACK SECTIONS
GENERAL ARRANGEMENT AND SPECIFICATION

 Scales (At A3) AS SHOWN Original Drawing size: A3 Drawing No. DL-TLG400-004	Design Eng: PD Drawn by: AW Drawing Status: INFORMATION	Checking Eng: JM Project Eng: SAB
	Rev. N1	

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.


Copyright © DLT Engineering Ltd.

NOTES


DUTY CHARTS ASSUME THE FOLLOWING:-

- STANDARD DL-TLG400 COMPONENTS WITH DL-TLG400 HEAD BEAM
- 2 No. LIFT POINTS EQUALLY LOADED PER HEAD BEAM
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%
- DL-TLG400 STANDARD TRACK SECTIONS USED WITH 1.0m RAIL CENTRES FOR TELESCOPIC CYLINDER STAGE 1 AND 1.7m RAIL CENTRES FOR TELESCOPIC CYLINDER STAGES 2 AND 3
- TABULATED LOADS APPLIED TO SHACKLE OR, IF SHACKLE NOT USED, TO SHACKLE BEAM

IF THE DL-TLG400 TELESCOPIC LIFTING GANTRY IS TO BE USED IN A CONFIGURATION NOT SHOWN ON THIS DRAWING, CONTACT DLT ENGINEERING FOR SPECIFIC SAFE WORKING LOADS AND ANY SPECIAL CONDITIONS THAT MAY APPLY



STAGE 1 : HEAD BEAM IN OPERATIONAL RANGE FROM LEVEL 3787 TO LEVEL 5787



STAGE 2 : HEAD BEAM IN OPERATIONAL RANGE TO LEVEL 7787
STAGE 3 : HEAD BEAM IN OPERATIONAL RANGE TO LEVEL 9287

SPAN 11.30m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES]					
STAGE	LIFT POINTS SPACING LPS [m]	LOAD CENTRE OFFSET E [m] FROM SPAN CENTRE			
		0.00	1.00	2.00	3.00
1	1.25	62.5	63.4	69.7	61.5
2		62.5	63.4	69.7	61.5
3		62.5	55.0	47.6	41.9
1	2.00	68.0	68.0	69.8	61.5
2		68.0	68.0	69.8	61.5
3		65.1	55.0	47.6	41.9
1	3.00	76.7	75.0	69.8	61.5
2		76.7	75.0	69.8	61.5
3		65.1	55.0	47.6	41.9
1	4.00	87.9	80.5	69.8	
2		87.9	80.5	69.8	
3		65.1	55.0	47.6	
1	5.00	95.1	80.5	69.8	
2		95.1	80.5	69.8	
3		65.1	55.0	47.6	
1	6.00	95.1	80.5		
2		95.1	80.5		
3		65.1	55.0		
1	7.00	95.1	80.5		
2		95.1	80.5		
3		65.1	55.0		
1	8.00	95.1			
2		95.1			
3		65.1			
1	9.00	95.1			
2		95.1			
3		65.1			

SPAN 10.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES]					
STAGE	LIFT POINTS SPACING LPS [m]	LOAD CENTRE OFFSET E [m] FROM SPAN CENTRE			
		0.00	1.00	2.00	3.00
1	1.25	72.5	73.9	67.4	58.8
2		72.5	73.9	67.4	58.8
3		65.1	53.9	46.0	40.1
1	2.00	79.8	78.9	67.4	58.8
2		79.8	78.9	67.4	58.8
3		65.1	53.9	46.0	40.1
1	3.00	91.9	78.9	67.4	58.8
2		91.9	78.9	67.4	58.8
3		65.1	53.9	46.0	40.1
1	4.00	95.1	78.9	67.4	
2		95.1	78.9	67.4	
3		65.1	53.9	46.0	
1	5.00	95.1	78.9	67.4	
2		95.1	78.9	67.4	
3		65.1	53.9	46.0	
1	6.00	95.1	78.9		
2		95.1	78.9		
3		65.1	53.9		
1	7.00	95.1	78.9		
2		95.1	78.9		
3		65.1	53.9		
1	8.00	95.1			
2		95.1			
3		65.1			
1	9.00	95.1			
2		95.1			
3		65.1			

SPAN 9.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES]					
STAGE	LIFT POINTS SPACING LPS [m]	LOAD CENTRE OFFSET E [m] FROM SPAN CENTRE			
		0.00	1.00	2.00	3.00
1	1.25	82.5	77.5	65.3	56.4
2		82.5	77.5	65.3	56.4
3		65.1	52.9	44.5	38.4
1	2.00	91.9	77.5	65.3	56.4
2		91.9	77.5	65.3	56.4
3		65.1	52.9	44.5	38.4
1	3.00	95.1	77.5	65.3	
2		95.1	77.5	65.3	
3		65.1	52.9	44.5	
1	4.00	95.1	77.5	65.3	
2		95.1	77.5	65.3	
3		65.1	52.9	44.5	
1	5.00	95.1	77.5	65.3	
2		95.1	77.5	65.3	
3		65.1	52.9	44.5	
1	6.00	95.1	77.5		
2		95.1	77.5		
3		65.1	52.9		
1	7.00	95.1			
2		95.1			
3		65.1			
1	8.00	95.1			
2		95.1			
3		65.1			

SPAN 8.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES]					
STAGE	LIFT POINTS SPACING LPS [m]	LOAD CENTRE OFFSET E [m] FROM SPAN CENTRE			
		0.00	1.00	2.00	3.00
1	1.25	95.1	75.7	62.8	
2		95.1	75.7	62.8	
3		65.1	51.7	42.8	
1	2.00	95.1	75.7	62.8	
2		95.1	75.7	62.8	
3		65.1	51.7	42.8	
1	3.00	95.1	75.7	62.8	
2		95.1	75.7	62.8	
3		65.1	51.7	42.8	
1	4.00	95.1	75.7		
2		95.1	75.7		
3		65.1	51.7		
1	5.00	95.1	75.7		
2		95.1	75.7		
3		65.1	51.7		
1	6.00	95.1			
2		95.1			
3		65.1			
1	7.00	95.1			
2		95.1			
3		65.1			

SPAN 7.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES]					
STAGE	LIFT POINTS SPACING LPS [m]	LOAD CENTRE OFFSET E [m] FROM SPAN CENTRE			
		0.00	1.00	2.00	3.00
1	1.25	95.1	73.6	59.9	
2		95.1	73.6	59.9	
3		65.1	50.2	40.8	
1	2.00	95.1	73.6	59.9	
2		95.1	73.6	59.9	
3		65.1	50.2	40.8	
1	3.00	95.1	73.6		
2		95.1	73.6		
3		65.1	50.2		
1	4.00	95.1	73.6		
2		95.1	73.6		
3		65.1	50.2		
1	5.00	95.1			
2		95.1			
3		65.1			
1	6.00	95.1			
2		95.1			
3		65.1			

SPAN 6.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES]					
STAGE	LIFT POINTS SPACING LPS [m]	LOAD CENTRE OFFSET E [m] FROM SPAN CENTRE			
		0.00	1.00	2.00	3.00
1	1.25	95.1	70.9		
2		95.1	70.9		
3		65.1	48.4		
1	2.00	95.1	70.9		
2		95.1	70.9		
3		65.1	48.4		
1	3.00	95.1	70.9		
2		95.1	70.9		
3		65.1	48.4		
1	4.00	95.1			
2		95.1			
3		65.1			
1	5.00	95.1			
2		95.1			
3		65.1			

INTERPOLATION BETWEEN TABULATED VALUES PERMISSIBLE
SEE ALSO OPERATION AND MAINTENANCE MANUAL

DLT Engineering
International House
Midland Road, Higham Ferrers
Northamptonshire, NN10 8DN
United Kingdom
Tel: +44 (0) 1933 319133
www.dlteng.com

Project
DL-TLG400
TELESCOPIC LIFTING GANTRY

Drawing Title
LIFTING ARRANGEMENT AND DUTY CHARTS
2 No. LIFT POINTS LOADED PER HEAD BEAM

Design Eng: JM Checking Eng: PD
Drawn by: SG Project Eng: SAB

Original Drawing size: A3
Drawing Status
INFORMATION

Drawing No. DL-TLG400-005-01 Rev. N1

DO NOT SCALE

This drawing has been produced by DLT Engineering in accordance with the instructions of the client for their sole and specific use.

DLT Engineering shall not be liable for the use of any information contained on this drawing for any purpose other than that for which it was specifically prepared and provided.

Should there be any doubt regarding the interpretation of any information given on this drawing, enquiries should be directed to DLT Engineering at the address given below before executing such part of the works.


Copyright © DLT Engineering Ltd.

NOTES


DUTY CHARTS ASSUME THE FOLLOWING:-

- STANDARD DL-TLG400 COMPONENTS WITH DL-TLG400 HEAD BEAM
- 1 No. LIFT POINT LOADED PER HEAD BEAM
- MAXIMUM HORIZONTAL LOAD = 5% OF VERTICAL LOAD IN ANY DIRECTION
- MAXIMUM SLOPE OF TRACK = 1% IN ANY DIRECTION (BOTH TRACKS AT SAME SLOPE WITHIN TOLERANCES SPECIFIED IN OPERATION AND MAINTENANCE MANUAL)
- MAXIMUM TRANSVERSE SLOPE OF HEAD BEAM = +/- 1%
- DL-TLG400 STANDARD TRACK SECTIONS USED WITH 1.0m RAIL CENTRES FOR TELESCOPIC CYLINDER STAGE 1 AND 1.7m RAIL CENTRES FOR TELESCOPIC CYLINDER STAGES 2 AND 3
- TABULATED LOADS APPLIED TO SHACKLE OR, IF SHACKLE NOT USED, TO SHACKLE BEAM

IF THE DL-TLG400 TELESCOPIC LIFTING GANTRY IS TO BE USED IN A CONFIGURATION NOT SHOWN ON THIS DRAWING, CONTACT DLT ENGINEERING FOR SPECIFIC SAFE WORKING LOADS AND ANY SPECIAL CONDITIONS THAT MAY APPLY



STAGE 1 : HEAD BEAM IN OPERATIONAL RANGE FROM LEVEL 3787 TO LEVEL 5787



**STAGE 2 : HEAD BEAM IN OPERATIONAL RANGE TO LEVEL 7787
STAGE 3 : HEAD BEAM IN OPERATIONAL RANGE TO LEVEL 9287**

SPAN 11.30m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES] SINGLE LIFT POINT LOADED					
STAGE	LIFT POINT OFFSET E [m] FROM SPAN CENTRE				
	0.00	1.00	2.00	3.00	4.00
1 AND 2	100.0	100.0	100.0	100.0	100.0
3	100.0	100.0	94.7	83.6	76.3

SPAN 10.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES] SINGLE LIFT POINT LOADED					
STAGE	LIFT POINT OFFSET E [m] FROM SPAN CENTRE				
	0.00	1.00	2.00	3.00	4.00
1 AND 2	100.0	100.0	100.0	100.0	100.0
3	100.0	100.0	91.4	79.8	72.4

SPAN 9.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES] SINGLE LIFT POINT LOADED					
STAGE	LIFT POINT OFFSET E [m] FROM SPAN CENTRE				
	0.00	1.00	2.00	3.00	4.00
1 AND 2	100.0	100.0	100.0	100.0	100.0
3	100.0	100.0	88.6	78.3	68.9

SPAN 8.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES] SINGLE LIFT POINT LOADED				
STAGE	LIFT POINT OFFSET E [m] FROM SPAN CENTRE			
	0.00	1.00	2.00	3.00
1 AND 2	100.0	100.0	100.0	100.0
3	100.0	100.0	85.3	74.5

SPAN 7.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES] SINGLE LIFT POINT LOADED				
STAGE	LIFT POINT OFFSET E [m] FROM SPAN CENTRE			
	0.00	1.00	2.00	3.00
1 AND 2	100.0	100.0	100.0	100.0
3	100.0	99.8	83.1	70.1

SPAN 6.00m SAFE WORKING LOAD (SWL) PER LIFT POINT [TONNES] SINGLE LIFT POINT LOADED			
STAGE	LIFT POINT OFFSET E [m] FROM SPAN CENTRE		
	0.00	1.00	2.00
1 AND 2	100.0	100.0	100.0
3	100.0	96.2	78.2

DLT Engineering
International House
Midland Road, Higham Ferrers
Northamptonshire, NN10 8DN
United Kingdom
Tel: +44 (0) 1933 319133
www.dlteng.com

Project
DL-TLG400
TELESCOPIC LIFTING GANTRY

Drawing Title
LIFTING ARRANGEMENT AND DUTY CHARTS
SINGLE POINT LOADED PER HEAD BEAM

Scales (At A3) AS SHOWN	Design Eng: JM	Checking Eng: PD
	Drawn by: SG	Project Eng: SAB

Original Drawing size: A3
Drawing Status
INFORMATION

Drawing No. **DL-TLG400-005-02** Rev. **N1**

INTERPOLATION BETWEEN TABULATED VALUES PERMISSIBLE
SEE ALSO OPERATION AND MAINTENANCE MANUAL